regulation shall be provided with amanufacturer'soperating manual, which is to be retained with the unit and which shall specify how to operate the incinerator within the limits described in paragraph 2 of appendix IV of this Annex. 38 Type Approval Certificates issued taking into account the Revised guidelines for the implementation of Annex Vof MARPOL (resolution MEPC.59(33), as amended by resolution MEPC.92(45)), or Standard specification for shipboard incinerators (resolution MEPC.76(40), as amended by resolution MEPC.93(45)), or the 2014 Standard specification for shipboard incinerators (resolution MEPC.244(66)), as amended by resolution MEPC.368(79). 39 Refer to the 2014 Standard specification for shipboard incinerators (resolution MEPC.244(66), as amended by resolution MEPC.368(79)), or Standard specification for shipboard incinerators (resolution MEPC.76(40), as amended by resolution MEPC.93(45)), and Type approval of shipboard incinerators (MEPC.1/Circ.793). RESOLUTION MEPC.403(83) (adopted on 11 April 2025) AMENDMENTS TO THE 2022 GUIDELINES ON SURVEY AND CERTIFICATION OF THE ENERGY EFFICIENCY DESIGN INDEX (EEDI)MEPC 83/17/Add.1 - RESOLUTION MEPC.403(83) (adopted on 11 April 2025) AMENDMENTS TO THE 2022 GUIDELINES ON SURVEY AND CERTIFICATION OF THE ENERGY EFFICIENCY DESIGN INDEX (EEDI)MEPC 83/17/Add.1 Annex 11, page 34 I:\MEPC\MEPC 83-17-Add.1.docx 8 Personnel responsible for the operation of an incinerator installed in accordance with the requirements of paragraph 6.1 of this regulation shall be trained to implement the guidance provided in the manufacturer'soperating manual as required by paragraph 7 of this regulation. 9 For incinerators installed in accordance with the requirements of paragraph 6.1 of this regulation the combustion chamber gas outlet temperature shall be monitored at all times the unit is in operation. Where that incinerator is of the continuous -feed type, waste shall not be fed into the unit when the combustion chamber gas outlet temperature is below 850°C. Where that incinerator is of the batch-loaded type, the unit shall be designed so that the combustion chamber gas outlet temperature shall reach 600 °Cwithin five minutes after start -up and will thereafter stabilize at atemperature not less than 850°C. Regulation 17 Reception facilities - chamber gas outlet temperature shall reach 600 °Cwithin five minutes after start -up and will thereafter stabilize at atemperature not less than 850°C. Regulation 17 Reception facilities 1 Each Party undertakes to ensure the provision of facilities adequate to meet the: .1 needs of ships using its repair ports for the reception of ozone -depleting substances and equipment containing such substances when removed from ships; .2 needs of ships using its ports, terminals or repair ports for the reception of exhaust gas cleaning residues from an exhaust gas cleaning system; without causing undue delay to ships, and .3 needs in ship -breaking facilities for the reception of ozone -depleting substances and equipment containing such substances when removed from ships. 2 The following States may satisfy the requirements in paragraph 1 of this regulation through regional arrangements when, because of those States ' unique ci