Inventory, because the information will be used to support ship recycling processes.
The Indicative list of materials listed in table B is shown below:

Materials Component of equipment
Cadmium and cadmium compounds Plating film, bearing
Hexavalent chromium compounds Plating film
Mercury and mercury compounds Fluorescent light, mercury lamp, mercury cell,
liquid-level switch, gyro compass, thermometer,
measuring tool, manganese cell, pressure sensors,
light fittings, electrical switches, fire detectors
Lead and lead compounds Corrosion resistant primer, solder (almost all electric
appliances contain solder), paints, preservative
coatings, cable insulation, lead ballast, generators

---CHUNK---

SOURCE: MEPC.379(80).pdf
light fittings, electrical switches, fire detectors
Lead and lead compounds Corrosion resistant primer, solder (almost all electric
appliances contain solder), paints, preservative
coatings, cable insulation, lead ballast, generators
Polybrominated biphenyls (PBBs) Non-flammable plastics
Polybrominated diphenyl ethers (PBDE) Non-flammable plastics
Polychlorinated naphthalenes Paint, lubricating oil
Radioactive substances Refer to appendix 10
Certain short-chain chlorinated paraffins Non-flammable plastics

3 STEP 2 ASSESSMENT OF COLLECTED INFORMATION

Preparation of a checklist is an efficient method for developing the Inventory for existing ships in order to clarify the results of each step. Based on collected information including the indicative list mentioned in step 1, all equipment, systems and/or areas on board assumed to contain hazardous material s listed in tables A and B should be included in the checklist. Each listed equipment, system and/or area on board should be analysed and assessed for its hazardous materials content.

The existence and volume of hazardous materials may be judged and calculated from the

---CHUNK---

SOURCE: MEPC.379(80).pdf
Each listed equipment, system and/or area on board should be analysed and assessed for its hazardous materials content.

The existence and volume of hazardous materials may be judged and calculated from the Spare parts and tools list and the maker's drawings. The existence of asbestos contained in floors, ceilings and walls may be identified from Fire Protection Plans, while the existence of TBT in coatings can be ident ified from the International Anti -Fouling System Certificate, Coating scheme and the History of Paint.

Example of weight calculation

No. Hazardous
Materials

Location/equipment/
component
Reference Calculation
1.1-2 TBT Flat bottom/paint History of coatings
1.2-1 Asbestos Main engine/
exh. pipe packing
Spare parts and
tools list
250 g x 14 sheet = 3.50 kg
1.2-3 HCFC Ref. provision plant Maker's drawings 20 kg x 1 cylinder = 20 kg
1.2-4 Lead Batteries Maker's drawings 6kg x 16 unit = 96 kg
1.3-1 Asbestos Engine-room ceiling Accommodation
plan

When a component or coating is determined to contain hazardous materials, a "Y" should be entered in the column for "Result of document analysis" in the checklist, to denote "Contained".

---CHUNK---

SOURCE: MEPC.379(80).pdf
1.3-1 Asbestos Engine-room ceiling Accommodation
plan

When a component or coating is determined to contain hazardous materials, a "Y" should be entered in the column for "Result of document analysis" in the checklist, to denote "Contained". Likewise, when an item is determined not to contain hazardous materials, the entry "N" should be made in the column to denote "Not contained". When a determination cannot be made as to the hazardous materials content, the column should be completed with the entry "Unknown".

4 STEP 3 PREPARATION OF VISUAL/SAMPLING CHECK PLAN

4.1 Each item classified as "Contained" or "Not contained" in step 2 should be subjected to a visual check on board, and the entry "V" should be made in the "Check procedure" column

---CHUNK---

SOURCE: MEPC.379(80).pdf
4 STEP 3 PREPARATION OF VISUAL/SAMPLING CHECK PLAN

4.1 Each item classified as "Contained" or "Not contained" in step 2 should be subjected to a visual check on board, and the entry "V" should be made in the "Check procedure" column to denote "Visual check".

4.2 For each item categorized as "unknown", a decision should be made as to whether to apply a sampling check. However, any item categorized as "unknown" may be classed as "potentially containing hazardous material" provided comprehensive justification is given, or if it can be assumed that there will be little or no effect on disassembly as a unit and later ship recycling and disposal operations. For example, in the following checklist, in order to carry out a sampling check for "Packing with aux. boiler " the shipowner needs to disassemble the auxiliary boiler in a repair yard. The costs of this check are significantly higher than the later disposal costs at a ship r ecycling facility. In this case, therefore, the classification as "potentially containing hazardous material" is justifiable.

RESOLUTION MEPC.379(80) (adopted on 7 July 2023)

---CHUNK---

SOURCE: MEPC.379(80).pdf
disposal costs at a ship r ecycling facility. In this case, therefore, the classification as "potentially containing hazardous material" is justifiable.

RESOLUTION MEPC.379(80) (adopted on 7 July 2023)

RESOLUTION MEPC.379(80) (adopted on 7 July 2023)

4.3 Before any visual/sampling check on board is conducted, a "visual/sampling check plan" should be prepared. An example of such a plan is shown below.

4.4 To prevent any incidents during the visual/sampling check, a schedule should be established to eliminate interference with other ongoing work on board. To prevent potential

exposure to hazardous materials during the visual/sampling check, safety precautions should be in place on board. For example, sampling of potential asbestos containing materials could release fibres into the atmosphere. Therefore, appropriate personnel safety and containment

---CHUNK---

SOURCE: MEPC.379(80).pdf
be in place on board. For example, sampling of potential asbestos containing materials could release fibres into the atmosphere. Therefore, appropriate personnel safety and containment procedures should be implemented prior to sampling.

4.5 Items listed in the visual/sampling check should be arranged in sequence so that the onboard check is conducted in a structured manner (e.g. from a lower level to an upper level and from a fore part to an aft part).

Example of visual/sampling check plan

Name of ship XXXXXXXXXX
IMO number XXXXXXXXXX
Gross tonnage 28,000 GT
L x B x D xxx.xx × xx.xx × xx.xx m
Date of delivery dd.mm.1987
Shipowner XXXXXXXXXX
Contact point
(Address, Telephone, Fax, Email)
XXXXXXXXXX
Tel: XXXX-XXXX