ADOPTION OF AMENDMENTS TO THE CODE FOR THE CONSTRUCTION AND EQUIPMENT OF MOBILE OFFSHORE DRILLING UNITS, 1989
THE MARITIME SAFETY COMMITTEE,
RECALLING Article 28(b) of the Convention on the International Maritime Organization concerning the functions of the Committee,
RECALLING ALSO that the Assembly, when adopting resolution A.649(16) on the Code for the Construction and Equipment of Mobile Offshore Drilling Units, 1989 (1989 MODU Code), authorized the Committee to amend the Code, when appropriate, taking into consideration the design and safety features after due consultation with appropriate organizations,
RECOGNIZING the significant contribution which is made by the 1989 MODU Code to the promotion of the safety of MODUs and property at sea and the lives of persons on board,
RECOGNIZING ALSO the need for introduction into this Code of provisions for survey and certification which are harmonized with corresponding

---CHUNK---

SOURCE: MSC.38(63).pdf
Code to the promotion of the safety of MODUs and property at sea and the lives of persons on board,
RECOGNIZING ALSO the need for introduction into this Code of provisions for survey and certification which are harmonized with corresponding provisions in other international instruments,
RECOGNIZING FURTHER the need for introduction into this Code of reference to Guidelines for vessels with dynamic positioning systems,
RECOGNIZING FURTHER the need for amendments to provisions for helicopter facilities,
HAVING CONSIDERED the recommendations made by the Sub-Committee on Ship Design and Equipment, at its thirty-seventh session, on introduction of the harmonized system of survey and certification (HSSC) into the 1989 MODU Code, on guidelines for vessels with dynamic positioning systems and on helicopter facilities,
1. ADOPTS amendments to the 1989 MODU code, set out in Annexes 1, 2 and 3 to the present resolution;
2. DECIDES that:
. 1 amendments introducing the HSSC should become effective on the same date as the 1988 SOLAS and Load Line Protocols relating to the HSSC; and
. 2 amendments for guidelines for vessels with dynamic positioning

---CHUNK---

SOURCE: MSC.38(63).pdf
2. DECIDES that:
. 1 amendments introducing the HSSC should become effective on the same date as the 1988 SOLAS and Load Line Protocols relating to the HSSC; and
. 2 amendments for guidelines for vessels with dynamic positioning systems and helicopter facilities should become effective on 1 July 1994;
W/1649n/EWP
RESOLUTION MSC.38(63)
(adopted on 19 May 1994)

3. AGREES that Governments that have informed IMO that they are introducing the HSSC under the terms of resolution A.7l8(17) before the entry into force of the 1988 SOLAS and Load Line Protocols should be permitted to also implement the HSSC in respect of the 1989 MODU Code provided that the mobile offshore drilling unit safety certificate is suitably endorsed;
4. INVITES all Governments concerned to take appropriate steps to give effect to the annexed amendments to the 1989 MODU Code.
W/1649n/EWP
RESOLUTION MSC.38(63)
(adopted on 19 May 1994)
ADOPTION OF AMENDMENTS TO THE CODE FOR THE CONSTRUCTION AND EQUIPMENT OF MOBILE OFFSHORE DRILLING UNITS, 1989 ANNEX 1

---CHUNK---

SOURCE: MSC.38(63).pdf
effect to the annexed amendments to the 1989 MODU Code.
W/1649n/EWP
RESOLUTION MSC.38(63)
(adopted on 19 May 1994)
ADOPTION OF AMENDMENTS TO THE CODE FOR THE CONSTRUCTION AND EQUIPMENT OF MOBILE OFFSHORE DRILLING UNITS, 1989 ANNEX 1

AMENDMENTS TO THE CODE FOR THE CONSTRUCTION AND EQUIPMENT OF MOBILE OFFSHORE DRILLING UNITS, 1989, TO HARMONIZE THE SURVEY AND CERTIFICATION WITH THE REQUIREMENTS OF THE 1988 SOLAS AND LOAD LINE PROTOCOLS
Add a new definition to 1.3 to read as follows:
"1.3.51 _ Anniversary date means the day and month of each year which will corres -pond to the date of expiry of the certificate".
The text of "1.6 Surveys and certification" should be replaced by the
, \' ~ t 't - ' ..
f 0 I-limn ng:
"1.6.1 Each unit should be subject to the surveys specified below:
. 1 an initial survey before the unit is put in service or before the certificate is issued for the first time;
. 2 a renewal survey at intervals specified by the Administration but not exceeding 5 years except where 1.6.11.2.1 or 1.6.11.5 or 1.6.11.6 is applicable;
.3 an intermediate survey within three months before or after the

---CHUNK---

SOURCE: MSC.38(63).pdf
. 2 a renewal survey at intervals specified by the Administration but not exceeding 5 years except where 1.6.11.2.1 or 1.6.11.5 or 1.6.11.6 is applicable;
.3 an intermediate survey within three months before or after the

second anniversary date or within three months before or after the
third anniversary date of the certificate, which should take the
place of one of the annual surveys specified in 1.6.1.4;
.4 an annual survey within three months before or after each
anniversary date of the certificate;
.5 a minimum of two drydock surveys during any five year period, except
where 1.6.11.5 is applicable. Where 1.6.11.5 is applicable this
fi v e year period may be extended to coincide with the extended
period of the validity of the certificate. In all cases the
intervals between any two such surveys should not exceed 36 months;
.6 radio station surveys in accordance with 11.10;
.7 an additional survey as the occasion arises.
1.6.2 The surveys referred to in 1 . 6.1 should be carried out as follows:
. 1 the initial survey should include a complete inspection of the
structure, safety equipment and other equipment, fittings,

---CHUNK---

SOURCE: MSC.38(63).pdf
1.6.2 The surveys referred to in 1 . 6.1 should be carried out as follows:
. 1 the initial survey should include a complete inspection of the
structure, safety equipment and other equipment, fittings,
arrangements and material to ensure that they comply with the
requirements of the Code, are in satisfactory condition and are fit
for the service for which the unit is intended;
. 2 the renewal survey should include an inspection of the structure,
safety equipment and other equipment as referred to in 1.6.2.1 to
ensure that they comply with the requirements of the Code, are in
satisfactory condition and are fit for the service for which the
unit is intended;
W/1649n / EWP
RESOLUTION MSC.38(63)
(adopted on 19 May 1994)
ADOPTION OF AMENDMENTS TO THE CODE FOR THE CONSTRUCTION AND EQUIPMENT
OF MOBILE OFFSHORE DRILLING UNITS, 1989 MSC 63/23/Add.1
ANNEX 20
Page 4
. 3 the intermediate survey should include an incpecLion of the
structure, fittings, arrangements and safety equipment to ensure
that they remain satisfactory for the service for which the unit is
intended;
.4 the annual survey should include a general inspection of the

---CHUNK---

SOURCE: MSC.38(63).pdf
structure, fittings, arrangements and safety equipment to ensure
that they remain satisfactory for the service for which the unit is
intended;
.4 the annual survey should include a general inspection of the
structure, safety equipment and other equipment as referred to in
1.6.2.1, to ensure that they have been maintained in accordance with
1.6.6.1 and that they remain satisfactory for the service for which
the unit is intended;

. 5 the drydock survey and the inspection of items surveyed at the same time should be such as to ensure that they remain satisfactory for the service for which the unit is intended. An Administration may allow underwater inspections in lieu of a drydock survey provided that they are satisfied that such an inspection is equivalent to a drydock survey;
.6 the radio survey should include a complete inspection of the radio installation to ensure that it complies with the requirements of the Code, is in satisfactory condition and is fit for the service for which the unit is intended;
. 7 an additional survey, either general or partial according to the circumstances, should be made after a repair resulting from

---CHUNK---

SOURCE: MSC.38(63).pdf
Code, is in satisfactory condition and is fit for the service for which the unit is intended;
. 7 an additional survey, either general or partial according to the circumstances, should be made after a repair resulting from
investigations prescribed in 1.6.6.3, or wherever any important repairs or renewals are made. The survey should be such as to ensure that the necessary repairs or renewals have been effectively