SOURCE: MEPC.59(33).pdf
A1.6.3 ON-BOARD OPERATION/EMISSION CONTROL
For a shipboard incinerator with IMO TYPE APPROVAL, emission control/monitoring should be limited to the following:
.1 Control/monitor 02 content in combustion chamber (spot checks only) .
. 2 Control/monitor temperature in combustion chamber flue gas outlet.
By continuous (auto) control of the incineration process, ensure that the above mentioned two parameters are kept within the prescribed limits. This mode of operation will ensure that particulates and ash residue contain only traces of organic constituents.
A1.7 PASSENGER/CRUISE SHIPS WITH INCINERATOR INSTALLATIONS HAVING A TOTAL CAPACITY OF MORE THAN 1,160 kW
A1.7.l On board this type of vessel, the following conditions will probably exist:
.1 Generation of huge amounts of burnable waste with a high content of plastic and synthetic materials .
2 Incinerating plant with a high capacity operating continuously over long periods
3 This type of vessel will often be operating in very sensitive coastal areas.
A1.7.2 In view of the fuel related emission from a plant with such a high capacity , installation of a flue gas sea water scrubber should be

---CHUNK---

SOURCE: MEPC.59(33).pdf
long periods
3 This type of vessel will often be operating in very sensitive coastal areas.
A1.7.2 In view of the fuel related emission from a plant with such a high capacity , installation of a flue gas sea water scrubber should be considered. This installation can perform an efficient after-cleaning of the flue gases, thus minimizing the content of:
HC1
SOX
PARTICULATE MATTER
A1.7.3 Any restriction on NITROGEN OXIDE (NOX) should only be considered in connection with possible future regulations on pollution from the vessel's total pollution, i.e., main and auxiliary machinery, boilers, etc.
W/9096D/ljt/EWP
RESOLUTION MEPC.59(33)
adopted on 30 October 1992
REVISED GUIDELINES FOR THE IMPLEMENTATION OF
ANNEX V OF MARPOL 73/78MEPC 33/20/Add.1
ANNEX 2
Page 18
A2 - FIRE PROTECTION REQUIREMENTS FOR INCINERATORS AND WASTE STOWAGE SPACES
For the purpose of construction, arrangement and insulation, incinerator spaces and waste stowag e spaces should be treated as category A machinery spaces (SOLAS II-2/3.19) and service spaces, (SOLAS 11-2/3.12), respectively.
To minimize the fire hazards these spaces represent, the following SOLAS

---CHUNK---

SOURCE: MEPC.59(33).pdf
spaces and waste stowag e spaces should be treated as category A machinery spaces (SOLAS II-2/3.19) and service spaces, (SOLAS 11-2/3.12), respectively. To minimize the fire hazards these spaces represent, the following SOLAS requirements in chapter 11-2 should be applied:
A2.1 For passenger vessels carrying more than 36 passenger:
.1 regulation 26.2.2(12) should apply to incinerator and combined incinerator/waste storage spaces, and the flue uptakes from such spaces; and
. 2 regulation 26.2.2(13) should apply to waste storage spaces and garbage chutes connected thereto.
A2.2 For all other vessels including passenger vessels carrying not more than 36 passengers:
. 1 regulation 44.2.2(6) should apply to incinerator and combined incinerator/waste spaces, and the flue uptakes from such spaces; and
.2 regulation 44.2.2(9) should apply to waste storage spaces and garbage chutes connected thereto.
A2.3 Incinerators and waste stowage spaces located on weather decks (regulation 11-2/3.(17» need not meet the above requirements but should be located:
.1 as far aft on the vessel as possible,
. 2 not less than 3 m from entrances, air inlets and openings

---CHUNK---

SOURCE: MEPC.59(33).pdf
(regulation 11-2/3.(17» need not meet the above requirements but should be located:
.1 as far aft on the vessel as possible,
. 2 not less than 3 m from entrances, air inlets and openings to accommodations, service spaces and control stations,
. 3 not less than 5 m measured horizontally from the nearest hazardous area, or vent outlet from a hazardous area; and
.4 not less than 2 m should separate the incinerator and the waste material storage area, unless physically separated by a structural fire barrier.
A2.4 A fixed fire detection and fire-extinguishing system should be installed in enclosed spaces containing incinerators, in combined incinerator/waste storage spaces, and in any waste storage space in accordance with the following table:
W/9096D/ljt/EWP
RESOLUTION MEPC.59(33)
adopted on 30 October 1992
REVISED GUIDELINES FOR THE IMPLEMENTATION OF ANNEX V OF MARPOL 73/78Combined incinerator and waste storage space
Incinerator space
Waste storage space
Automatic sprinkler system

X
X
MEPC 33/20/Add.l
ANNEX 2
Page 19
Fixed fire
extinguishing
system
X
Fixed fire
detection
system
X

---CHUNK---

SOURCE: MEPC.59(33).pdf
waste storage space
Incinerator space
Waste storage space
Automatic
sprinkler
system
X
X
MEPC 33/20/Add.l
ANNEX 2
Page 19
Fixed fire
extinguishing
system
X
Fixed fire
detection
system
X
A2 . 5 Where an incinerator or waste storage space is located on weather decks it must be accessible with two means of fire extinguishment; either fire hoses, semi-portable fire extinguishers, fire monitors or combination of any two of these extinguishing devices. A fixed fire-extinguishing system is acceptable as one means of extinguishment.
A2.6 Flue uptake piping/ducting should be led independently to an appropriate terminus via a continuous funnel or trunk.
A3 - INCINERATORS INTEGRATED WITH HEAT RECOVERY UNITS
A3.l The flue gas system, for incinerators where the flue gas is led through a heat recovery device, should be designed so that the incinerator can continue operation with the economizer coils dry. This may be accomplished with bypass dampers if needed.
A3.2 The incinerator unit should be equipped with a visual and an audible alarm in case of loss of feed-water.
A3.3 The gas-side of the heat recovery device should have equipment for

---CHUNK---

SOURCE: MEPC.59(33).pdf
with bypass dampers if needed.
A3.2 The incinerator unit should be equipped with a visual and an audible alarm in case of loss of feed-water.
A3.3 The gas-side of the heat recovery device should have equipment for proper cleaning. Sufficient access should be provided for adequate inspection of external heating surfaces.
A4 - FLUE GAS TEMPERATURE
A4.1 When deciding upon the type of incinerator, consideration should be given as to what the flue gas temperature will be. The flue gas temperature can be a determining factor in the selection of materials for fabricating the stack. Special high temperature material may be required for use in fabricating the stack when the flue gas temperatures exceed 430°C.
W/9096D/ljt/EWP
RESOLUTION MEPC.59(33)
adopted on 30 October 1992
REVISED GUIDELINES FOR THE IMPLEMENTATION OF
ANNEX V OF MARPOL 73/78MEPC 33/20/Add.1
ANNEX 2
Page 20
ANNEX
FORM OF IMO TYPE APPROVAL CERTIFICATE FOR
SHIPBOARD INCINERATORS WITH CAPACITIES OF UP TO 1,160 KW