contained in part 3 of the annex to resolution MEPC.107(49).

4.1.2 Where a range of add-on equipment of the same design, but of different capacities, requires certification in accordance with these specifications, the Administration may accept

---CHUNK---

SOURCE: MEPC.205(62).pdf
contained in part 3 of the annex to resolution MEPC.107(49).

4.1.2 Where a range of add-on equipment of the same design, but of different capacities, requires certification in accordance with these specifications, the Administration may accept tests in two capacities within the range, in lieu of tests on every size, providing that the two tests actually performed are from the lowest quarter and highest quarter of the range.

4.2 Approval and certification procedures

Add-on equipment which in every respect fulfils the provisions of these Guidelines may be approved by the Administration for fitting on board ships. The approval should take the form of a certificate of type approval specifying the main particulars of the apparatus and any limiting conditions on its usage necessary to ensure its proper performance. Such certificate should be issued in the format shown in part 3 of the annex.

5 INSTALLATION REQUIREMENTS

5.1 Before installation of add-on equipment, it is important to ascertain that the existing oil filtering equipment is well maintained and in good working condition and that the rated capacity match that of add-on equipment.

---CHUNK---

SOURCE: MEPC.205(62).pdf
5.1 Before installation of add-on equipment, it is important to ascertain that the existing oil filtering equipment is well maintained and in good working condition and that the rated capacity match that of add-on equipment.

5.2 The add-on equipment should be instal led between the existing oil filtering equipment and the sampling point provided for inspection purposes on board ship.

5.3 The add-on equipment should be fitted with a permanently attached plate giving any operational or installation limits considered necessary by the manufacturer or by the Administration.

5.4 A vessel fitted with an add-on equipment should, at all times, have on board a copy of the operating and maintenance manuals.

5.5 For inspection purposes on board ship, a sampling point should be provided in a vertical section of the water effluent piping as close as is practicable to the 15 ppm bilge separator and add-on equipment outlet. Re-circulating facilities should be provided, after and adjacent to the overboard outlet of the stopping device to enable the 15 ppm bilge separator system, including the 15 ppm bilge alarm and the automatic stopping device where

---CHUNK---

SOURCE: MEPC.205(62).pdf
and adjacent to the overboard outlet of the stopping device to enable the 15 ppm bilge separator system, including the 15 ppm bilge alarm and the automatic stopping device where fitted, to be tested with the overboard discharge closed.

5.6 Where fitted, the bilge alarm should be approved according to resolution MEPC.107(49).

RESOLUTION MEPC.205(62)
Adopted on 15 July 2011
2011 GUIDELINES AND SPECIFICATIONS FOR ADD-ON EQUIPMENT FOR UPGRADING RESOLUTION MEPC.60(33)-COMPLIANT OIL FILTERING EQUIPMENTMEPC 62/24/Add.1
Annex 24, page 6

I:\MEPC\62\24-Add-1.doc
ANNEX

TEST AND PERFORMANCE SPECIFICATIONS FOR TYPE APPROVAL OF ADD-ON EQUIPMENT FOR UPGRADING RESOLUTION MEPC.60(33)-COMPLIANT OIL FILTERING EQUIPMENT

PART 1

ADD-ON EQUIPMENT TO BE FITTED TO SPECIFIC OIL FILTERING EQUIPMENT APPROVED UNDER RESOLUTION MEPC.60(33)

1 General

1.1 These test and performance specifications for type approval relate to add-on equipment for oil filtering equipment type approved in accordance with resolution MEPC.60(33) (hereinafter referred to as "oil filtering equipment"). In addition, the electrical

---CHUNK---

SOURCE: MEPC.205(62).pdf
equipment for oil filtering equipment type approved in accordance with resolution MEPC.60(33) (hereinafter referred to as "oil filtering equipment"). In addition, the electrical and electronic systems of the add-on equipment should be tested in accordance with the specifications for environmental testing contained in part 3 of resolution MEPC.107(49).

1.2 The test of add-on equipment should be carried out in combination with oil filtering equipment to which add-on equipment being tested is intended to be added on.

2 Test specifications

2.1 These specifications relate to add-on equipment for oil filtering equipment. A set of oil filtering equipment and add-on equipment should be capable of producing an effluent for discharge to the sea containing not more than 15 ppm of oil, when 3,000 ppm oil in water emulsions are fed.

2.2 The test rig must be so constructed as to include not only oil filtering equipment and add-on equipment, but also the pumps, valves, pipes and fittings as shown in figure 1:

.1 for the testing of oil filtering equipment having no integral pump, the centrifugal pump "A" (figure 1) is us ed to feed oil filtering equipment with

---CHUNK---

SOURCE: MEPC.205(62).pdf
add-on equipment, but also the pumps, valves, pipes and fittings as shown in figure 1:

.1 for the testing of oil filtering equipment having no integral pump, the centrifugal pump "A" (figure 1) is us ed to feed oil filtering equipment with valves 2 and 4 open, and valve 3 closed. The rate of flow from the centrifugal pump "A" is matched to the design throughput of oil filtering equipment by adjustment of the centrifugal pump's discharge valve;

.2 a centrifugal pump "B" should be fitted to re-circulate the test fluid "C" in the tank to ensure that the test fluid "C" is maintained in a stable condition throughout the testing;

.3 to ensure a good mix of the test fluid and the water, a conditioning pipe as specified in paragraph 2.4 should be fitted immediately before oil filtering equipment;

.4 other valves, flow meters and sample points should be fitted to the test rig as shown in figure 1; and

.5 the pipe work should be designed for a maximum liquid velocity of 3 metres/second.
RESOLUTION MEPC.205(62)
Adopted on 15 July 2011
2011 GUIDELINES AND SPECIFICATIONS FOR ADD-ON EQUIPMENT FOR UPGRADING RESOLUTION

---CHUNK---

SOURCE: MEPC.205(62).pdf
as shown in figure 1; and

.5 the pipe work should be designed for a maximum liquid velocity of 3 metres/second.
RESOLUTION MEPC.205(62)
Adopted on 15 July 2011
2011 GUIDELINES AND SPECIFICATIONS FOR ADD-ON EQUIPMENT FOR UPGRADING RESOLUTION MEPC.60(33)-COMPLIANT OIL FILTERING EQUIPMENTMEPC 62/24/Add.1
Annex 24, page 7

Figure 1 Test rig

2.3 Tests should be performed using test fluid "C" as defined in resolution MEPC.107(49).

2.4 If oil filtering equipment includes an integrated feed pump, oil filtering equipment and add-on equipment should be tested with that pump supplying the required quantity of test fluid and water to oil filtering equipment at its rated capacity. If oil filtering equipment is to be fed by the ship's pumps, then the unit will be tested by supplying the required quantity of test fluid and water mixture to the inlet of a centrifugal pump operating at not less than 1,000 rpm (see dotted line in figure 1). This pump should have a delivery capacity of not less