than 1.1 times the rated capacity of oil filtering equipment at the delivery pressure required

---CHUNK---

SOURCE: MEPC.205(62).pdf
(see dotted line in figure 1). This pump should have a delivery capacity of not less than 1.1 times the rated capacity of oil filtering equipment at the delivery pressure required for the test. If a centrifugal pump is used, the excess pump capacity should be controlled by a throttle valve on the discharge side of the pump. In all cases, to ensure uniform conditions, the piping arrangements immediately prior to oil filtering equipment should be such that the influent to oil filtering equipment should have a Reynolds number of not less than 10,000 as calculated in fresh water, a liquid velocity of not less than 1 metre per second and the length of the supply pipe from the point of test fluid injection to oil filtering equipment should have a length not less than 20 times its diameter. A mixture inlet sampling point and a thermometer pocket should be provided near oil filtering equipment inlet and an outlet sampling point and observation window should be provided on the discharge pipe.
Sample point
Sample point Sample point
Sample point
Filtering
P
Effluent
Water
(clean water)
Centrifugal pump
B
Centrifugal pump
A
V1 V2
V3
V4
V5
FM
FM
Flowmeter

---CHUNK---

SOURCE: MEPC.205(62).pdf
observation window should be provided on the discharge pipe.
Sample point
Sample point Sample point
Sample point
Filtering
P
Effluent
Water
(clean water)
Centrifugal pump
B
Centrifugal pump
A
V1 V2
V3

V4
V5
FM
FM
Flowmeter
Conditioning pipe
Observation
window
P
Test fluid
"C"
Equipment
Add-on
Equipment
RESOLUTION MEPC.205(62)
Adopted on 15 July 2011
2011 GUIDELINES AND SPECIFICATIONS FOR ADD-ON EQUIPMENT FOR UPGRADING RESOLUTION MEPC.60(33)-COMPLIANT OIL FILTERING EQUIPMENTMEPC 62/24/Add.1
Annex 24, page 8

I:\MEPC\62\24-Add-1.doc

Figure 2 Diagram of sampling arrangements

A Distance A, not greater than 400 mm
B Distance B, sufficient to insert sampling bottle
C Dimension C, straight length should not be less than 60 mm
D Dimension D, pipe thickness should not be greater than 2 mm
E Detail E, chisel-edged chamfer (30)

2.5 In order to approach isokinetic sampling i.e. the sample enters the sampling pipe at stream velocity the sampling arrangement should be as shown in figure 2 and, if a cock is fitted, free flow should be effected for at least one minute before any sample is taken.

---CHUNK---

SOURCE: MEPC.205(62).pdf
at stream velocity the sampling arrangement should be as shown in figure 2 and, if a cock is fitted, free flow should be effected for at least one minute before any sample is taken. The sampling points should be in pipes running vertically.

2.6 In the case of oil filtering equipment and add-on equipment depending essentially on gravity, the feed to the system of the test water and test fluid mixture should be maintained at a temperature not greater than 40ºC, and heating and cooling coils should be provided where necessary. The water shall have a density of not more than 1.015 at 20ºC. In other forms of separation where the dependence of separation efficiency on temperature is not established, tests should be carried out over a range of influent temperatures representing the normal shipboard operating range of 10ºC to 40ºC or should be taken at a temperature in this range where the separation efficiency is known to be worst.

2.7 In those cases where, for oil filtering equipment and add-on equipment, it is

necessary to heat water up to a given temperature and to supply heat to maintain that

---CHUNK---

SOURCE: MEPC.205(62).pdf
where the separation efficiency is known to be worst.

2.7 In those cases where, for oil filtering equipment and add-on equipment, it is necessary to heat water up to a given temperature and to supply heat to maintain that temperature, the tests should be carried out at the given temperature.

2.8 The tests with test fluid "C" should be carried out as follows:

.1 prior to the test with test fluid "C", oil filtering equipment and add-on equipment should be filled up with water (density of not more than 1.015 at 20ºC);

.2 oil filtering equipment and add-on equipment should be fed with a mixture composed of 6% test fluid "C" and 94% water to have emulsified oil content of 3,000 ppm in the test water until steady conditions have been established. Steady conditions are assumed to be the conditions established after pumping through oil filtering equipment and add-on

---CHUNK---

SOURCE: MEPC.205(62).pdf
of 3,000 ppm in the test water until steady conditions have been established. Steady conditions are assumed to be the conditions established after pumping through oil filtering equipment and add-on equipment a quantity of test fluid "C"/water mixture not less than twice the volume of oil filtering and add-on equipment; and

.3 the test should then proceed for 2.5 h. Samples should be taken at the effluent outlet at 50 minutes and 100 minutes after conditioning. At the end of this test, an air cock should be opened on the suction side of the pump and, if necessary, the test fluid "C " and water valves should be slowly closed together, and a sample taken at the effluent discharge as the flow ceases (this point can be checked from the observation window).

2.9 Sampling should be carried out as shown in figure 2 so that the sample taken will suitably represent the fluid issuing from the effluent outlet of add-on equipment.

2.10 Samples should be taken in accordance with ISO 93772:2000. The sample is to be extracted on the same day of collection, and be sealed and labelled in the presence of a

---CHUNK---

SOURCE: MEPC.205(62).pdf
2.10 Samples should be taken in accordance with ISO 93772:2000. The sample is to be extracted on the same day of collection, and be sealed and labelled in the presence of a representative of the national authority and arrangements should be made for analysis as soon as possible and in any case within seven days, provided the samples are being kept between 2ºC and 6ºC at laboratories approved by the Administration.

2.11 The oil content of the samples should be determined in accordance with part 4 of the annex to resolution MEPC.107(49).

2.12 When accurate and reliable oil content meters are fitted at inlet and outlet of add-on equipment, one sample at inlet and outlet taken during each test will be considered sufficient if they verify, to within ±10%, the meter readings noted at the same instant.

PART 2

ADD-ON EQUIPMENT TO BE FITTED TO ANY OIL FILTERING EQUIPMENT

3 General

These test and performance specifications for type approval relate to add-on equipment for any oil filtering equipment type-approved in accordance with resolution MEPC.60(33).