within, on, or immediately adjacent to fuel tanks that contain or have last contained fuel;

on pipelines, heating coils, pump fittings or other accessories connected to spaces that contain or have last contained fuel; and

bilges, cargo holds, engine room spaces and boiler spaces not containing dangerous atmospheres.

The Ship Recycling Facility should ensure that no hot work commences in any of these spaces until Safe-for-hot-work certification has been issued by a Competent person; these inspections and tests should be entered on the record of inspection and testing and posted in a conspicuous place on board. A Competent person should visually inspect and test each space on the ship to determine the areas which are deemed "Safe-for-hot-work" before a certificate is issued and before recycling activities commence.

3.3.4.2.1 Safe-for-hot-work criteria

---CHUNK---

SOURCE: MEPC.210(63).pdf
space on the ship to determine the areas which are deemed "Safe-for-hot-work" before a certificate is issued and before recycling activities commence.

3.3.4.2.1 Safe-for-hot-work criteria

A space that is "Safe-for-hot-work" is one that meets all the Safe-for-entry criteria and also the following criteria:

any residues or materials in the space are not capable of producing an oxygen-enriched or oxygen-deficient environment, and are not capable of generating flammable or explosive vapours;

all adjacent spaces have been cleaned, rendered inert or sufficiently treated to prevent the risk of explosion, the release of noxious or toxic fumes or gases and the spread of fire; and

work in adjacent spaces is not affected by the hot work, such as tank entry, lifting operations or deconstruction by hand.

3.3.4.2.2 Competent person for Safe-for-hot-work determination

A Competent person for matters related to Safe-for-hot-work determination should meet the

---CHUNK---

SOURCE: MEPC.210(63).pdf

lifting operations or deconstruction by hand.

3.3.4.2.2 Competent person for Safe-for-hot-work determination

A Competent person for matters related to Safe-for-hot-work determination should meet the criteria identified in 3.3.4.1 and possess the additional knowledge and skills required to handle hot work activities.

3.3.4.2.3 Safe-for-hot-work inspection, testing and determination

Each space should be certified by a Competent person as "Safe-for-hot-work" as often as necessary to ensure that conditions within that space are maintained as established by the certificate. The frequency with which a space should be monitored to determine whether conditions are being maintained is a function of the following, but should in any event not exceed an eight-hour shift period:

temperature: any changes in temperature in the space could result in a change in its atmospheric conditions, and hotter days can cause residues to produce more vapours, resulting in a greater risk of flammable or explosive conditions;

work in the space: activity in the space can change its atmospheric conditions;

---CHUNK---

SOURCE: MEPC.210(63).pdf
in its atmospheric conditions, and hotter days can cause residues to produce more vapours, resulting in a greater risk of flammable or explosive conditions;

work in the space: activity in the space can change its atmospheric conditions; gas leaks from a hose or torch or m anual tank cleaning by scraping or using hand-held high-pressure spray devices can stir up residues, which can result in a greater risk of flammable or explosive conditions;

period of elapsed time: if a sufficient period of time (not to exceed 24 hours) has elapsed since Safe-for-hot-work certificate was issued, the condition of the space should be retested prior to entry and commencement of work;

unattended spaces: a tank or space that has been certified as "Safe-for-hot-work" then subsequently left unattended for a sufficient period of time should be retested prior to entry and commencement of work;

work break: tanks or spaces should be checked for equipment left behind when workers take a break or leave at the end of the shift, and the condition of the tank or space should be retested prior to entry and resumption of work; and

---CHUNK---

SOURCE: MEPC.210(63).pdf
work break: tanks or spaces should be checked for equipment left behind when workers take a break or leave at the end of the shift, and the condition of the tank or space should be retested prior to entry and resumption of work; and

ballasting or trimming: changing the position of the ballast or moving or trimming the ship in any way can produce a change in the atmosphere of the spaces; the

condition of the spaces should be retested prior to entry and resumption of work.

3.3.4.2.4 Safe-for-hot-work certificate, warning signs and labels

Any determination of a space as "Safe-for-hot-work" should be accompanied by a certificate which, at a minimum, should include the information identified in section 3.3.4.1.8 ("Safe-for-entry certificate, warning signs and labels"). Warning signs and labels should be posted in the manner described in section 3.3.4.1.8 for Safe-for-entry determination, clearly indicating that the space is "Safe-for-hot-work".

3.3.4.2.5 Safe-for-hot-work operational measures

---CHUNK---

SOURCE: MEPC.210(63).pdf
RESOLUTION MEPC.210(63)
Adopted on 2 March 2012
2012 GUIDELINES FOR SAFE AND ENVIRONMENTALLY SOUND SHIP RECYCLINGMEPC 63/23
Annex 4, page 19

I:\MEPC\63\23.doc
3.3.4.2.5 Safe-for-hot-work operational measures

In addition to the measures identified in section 3.3.4.1.9 ("Safe-for-entry operational measures"), the following should also be appli ed in order to achieve certification as "Safe-for-hot-work":

- each area where hot work is to be performed should be carefully prepared and isolated before hot work commences;

- all trash, debris, oil residues or other materials that could generate flammable or explosive vapours should be removed from the space prior to commencing hot work. The space and adjacent spaces should be kept free of any trash, debris, oil residues or other materials that could result in a risk of flammable or explosive conditions;

- drums and similar small containers which have contained flammable substances should, before they are cut, be either filled with water or thoroughly cleaned of such substances;

- deck tanks should be appropriately cleaned, gas freed and certified

---CHUNK---

SOURCE: MEPC.210(63).pdf
substances should, before they are cut, be either filled with water or thoroughly

cleaned of such substances;

deck tanks should be appropriately cleaned, gas freed and certified as Safe-for-entry and tested for hot work as described in the general sections (see sections 3.3.4.1 and 3.3.4.2). A suitable supply of fresh air should be maintained, given that oxygen from the atmosphere may be removed in the combustion process. The tanks should be isolated and tested in accordance with the guidance given in these guidelines. Particular attention should be paid to access and egress and to the unique challenges presented by these spaces regarding tank rescue in an emergency situation;

fixed cargo or fuel tanks should be cleaned and ventilated before any work commences and after having been passed as "Safe-for-entry" and "Safe-for-hot-work". Cleaning should be sufficient to remove any hazardous liquids, light solids and clinkage to allow the tank to be gas freed. Complex structures may require additional preparation before being certified as "Safe-for-hot-work". The need for localized manual cleaning should be

---CHUNK---

SOURCE: MEPC.210(63).pdf
hazardous liquids, light solids and clinkage to allow the tank to be gas freed. Complex structures may require additional preparation before being certified as