5 DFT measurements should be taken to prove that the coating has been applied to the thickness as specified and outlined in annex 3.

Construction
stage
Inspection items
1 Visual inspection for steel surface condition, surface preparation and verification of conformance to other requirements in table 1, and the agreed

---CHUNK---

SOURCE: MSC.244(83).pdf
ANNEX 10
Page 14

I:\MSC\83\28-Add-2.doc
Construction
stage
Inspection items
1 Visual inspection for steel surface condition, surface preparation and verification of conformance to other requirements in table 1, and the agreed specification should be performed.

2 The surface temperature, the relative humidity and the dew point should be measured and recorded before coating starts and regularly during the coating process.

Erection
3 Inspection should be performed of the steps in the coating application process mentioned in table 1.

7 VERIFICATION REQUIREMENTS

The following should be carried out by the Administration prior to reviewing the Coating Technical File for the ship subject to this Standard:

.1 check that the Technical Data Sheet and Statement of Compliance or Type Approval Certificate comply with the Standard;

.2 check that the coating identification on representative containers is consistent with the coating identified in the Technical Data Sheet and Statement of Compliance or Type Approval Certificate;

.3 check that the inspector is qualified in accordance with the qualification standards in paragraph 6.1.1;

---CHUNK---

SOURCE: MSC.244(83).pdf
the coating identified in the Technical Data Sheet and Statement of Compliance or Type Approval Certificate;

.3 check that the inspector is qualified in accordance with the qualification standards in paragraph 6.1.1;

.4 check that the inspectors reports of surface preparation and the coatings application indicate compliance with the manufacturers Technical Data Sheet and Statement of Compliance or Type Approval Certificate; and

.5 monitor implementation of the coating inspection requirements.

8 ALTERNATIVE SYSTEMS

8.1 All systems that are not an epoxy-based syst em applied according to table 1 of this Standard are defined as alternative systems.

8.2 This Standard is based on recognized and commonly used co ating systems. It is not meant to exclude other, alternative, systems w ith proven equivalent performance, for example non epoxy-based systems.

8.3 Acceptance of alternative systems should be subject to documented evidence that they ensure a corrosion prevention performance at least equivalent to that indicated in this Standard.

8.4 As a minimum, the documented evidence sh ould consist of satisfactory performance

---CHUNK---

SOURCE: MSC.244(83).pdf
ensure a corrosion prevention performance at least equivalent to that indicated in this Standard.

8.4 As a minimum, the documented evidence sh ould consist of satisfactory performance corresponding to that of a coating system which conforms to the Standard as described in section 4, a target useful life of 15 years in either actual field exposure for five years with final coating condition not less than GOOD or labor atory testing. Laboratory tests should be conducted in accordance with the test procedure given in annex 1 of this Standard.

ANNEX 1

TEST PROCEDURE FOR COATING QUALIFICATION FOR VOID SPACES
OF BULK CARRIERS AND OIL TANKERS

1 Scope

This procedure provides details of the test procedure referred to in se ction 4, table 1, items .1.2 and .1.3 and paragraph 8.3 of this Standard.

2 Definition

Coating specification means the specification of coating systems which includes the type of

---CHUNK---

SOURCE: MSC.244(83).pdf
and .1.3 and paragraph 8.3 of this Standard.

2 Definition

Coating specification means the specification of coating systems which includes the type of coating system, steel preparation, surface pr eparation, surface cleanliness, environmental conditions, application procedure, acceptance criteria and inspection.

3 Test

Coating specification should be verified by a condensation chamber test in accordance with the procedures specified in this section.

3.1 Test condition

Condensation chamber tests should be conducted in accordance with ISO 6270.

.1 The exposure time should be 30 days.

.2 There should be 3 test panels .

.3 The size of each test panel should be 150 mm x 150 mm x 3 mm. All of the panels should be treated according to the Performance standard, tables 1, 2 and 3, and coating system applied according to table 1.1.4 and 1.1.5. At the primer stage, two of the panels s hould be weathered for at leas t 2 months and cleaned by low pressure washing or other mild me thod. Blast sweep or high pressure washing, or other primer removal methods should not be used. The third plate

---CHUNK---

SOURCE: MSC.244(83).pdf
stage, two of the panels s hould be weathered for at leas t 2 months and cleaned by low pressure washing or other mild me thod. Blast sweep or high pressure washing, or other primer removal methods should not be used. The third plate should have the primer removed to St 3 before the top coat is applied. Weathering method and extent should take into cons ideration that the primer should be the foundation for a 15 year target life system . To facilitate innovation, alternative preparation, coating system s and dry film thicknesses may be used when clearly defined.

.4 The reverse side of the test piece should be painted appropriately, in order not to affect the test results.

Water 40 ± 2 ° C
Test panels
Room temperature 23 ± 2 ° C
100 % RH

Figure 1: Condensation chamber

3.2 Test results

3.2.1 Prior to the testing, the following measured data of the coating system should be reported: