.3 ship size in DWT and/or GT, as applicable;

.4 ship's limited shaft / engine power and ship's maximum unlimited shaft / engine power;

.5 position of the ship and timestamp when the power reserve was used;

.6 reason for using the power reserve;

.7 Beaufort number and wave height or ice condition in case of using the power reserve under adverse weather condition;

.8 supporting evidence (e.g. expected weather condition) in case of using the

---CHUNK---

SOURCE: MEPC.335(76).pdf
.6 reason for using the power reserve;

.7 Beaufort number and wave height or ice condition in case of using the power reserve under adverse weather condition;

.8 supporting evidence (e.g. expected weather condition) in case of using the power reserve for avoidance action;

.9 records from the SHaPoLi / EPL system for the electronically control led engine during the power reserve was used; and

.10 position of the ship and timestamp when the power limit was reactivated or replaced.

3.3 Where an EPL/ShaPoLi override is activated but the power reserve is not subsequently used, this event should be recorded in the bridge and engine- room logbooks. The engine-room logbook should record power used during the period when the override was activated. The EPL/ShaPoLi should be reset as soon as possible, and details of the reset should also be recorded in the bridge and engine-room logbooks.

3.4 In case of having used a power reserve, the ship should without delay notify its Administration or RO responsible for issuing the relevant certificate and the competent authority of the relevant port of destination with the information recorded in accordance with

---CHUNK---

SOURCE: MEPC.335(76).pdf
Administration or RO responsible for issuing the relevant certificate and the competent authority of the relevant port of destination with the information recorded in accordance with paragraph 3.2. On an annual basis, the Administration should report uses of a power reserve to IMO with the information recorded in accordance with paragraph 3.2.

3.5 Once the risks have been mitigated, the ship should be operated below the certified level of engine power under the SHaPoLi / EPL. The SHaPoLi / EPL system should be reactivated or replaced by the crew immediately after the risks have been prevented and the ship can be safely operated with the limited shaft / engine power. The reactivation or replacement of the SHaPoLi / EPL system should be confirmed (e.g. validation of mechanical sealing) with supporting evidence (e.g. engine power log, photo taken at the occasion of

---CHUNK---

SOURCE: MEPC.335(76).pdf
replacement of the SHaPoLi / EPL system should be confirmed (e.g. validation of mechanical sealing) with supporting evidence (e.g. engine power log, photo taken at the occasion of resetting the mechanical sealing) by the Administration or the RO at the earliest opportunity.

3.6 Any defect of the SHaPoLi / EPL system should be reported to the Administration or RO responsible for issuing the relevant certificate in accordance with regulation 5.6 of MARPOL Annex VI.

3.7 The port State control officers should inspect whether the SHaPoLi / EPL system has been properly installed and used in accordance with the IEE Certificate and the OMM as described in section 4 of these Guidelines. If overriding of the SHaPoLi / EPL without proper notification in accordance with paragraph 3.3 of these Guidelines has been det ected, the reactivation or replacement of the SHaPoLi / EPL should be immediately conducted in the presence of the Administration or the RO at the port.

4 Onboard Management Manual (OMM) for SHaPoLi / EPL

4.1 The SHaPoLi / EPL system should be accompanied by the OMM for SHaPoLi / EPL that should be permanently on board the ship for inspection.

---CHUNK---

SOURCE: MEPC.335(76).pdf
4 Onboard Management Manual (OMM) for SHaPoLi / EPL

4.1 The SHaPoLi / EPL system should be accompanied by the OMM for SHaPoLi / EPL that should be permanently on board the ship for inspection.

4.2 The OMM for SHaPoLi / EPL should be verified by the Administration or the RO after a survey verifying the ship's attained EEXI, as required by regulation 5.4 of MARPOL Annex VI.

4.3 The OMM for SHaPoLi / EPL should, as a minimum, include:

.1 SHaPoLi:

.1 a technical description of the main system as specified in section 2 of these guidelines as well as relevant auxiliary systems;

.2 identification of key components of the system by manufacturer, model/type, serial number and other details as necessary;

.3 description of a verification procedure demonstrating that the system is in compliance with the technical description in accordance with items .1 and .2;

.4 the maximum shaft power for which the unit is designed;

.5 service, maintenance and calibration requirements of sensors according to sensor manufacturer and a description how to monitor the appropriateness of the calibration intervals, if applicable;

---CHUNK---

SOURCE: MEPC.335(76).pdf
.5 service, maintenance and calibration requirements of sensors according to sensor manufacturer and a description how to monitor the appropriateness of the calibration intervals, if applicable;

.6 the SHaPoLi record book for the recording of service, maintenance and calibration of the system;

.7 the description how the shaft power can be limited and unlimited and how this is displayed by the control unit as required by paragraph 2.2.5 of these Guidelines;

.8 the description of how the controller limits the power delivered to the propeller shaft;

.9 the identification of responsibilities;

.10 procedures for notification of the use of power reserve and the detections of malfunctions of the system in accordance with paragraphs 3.4 and 3.5 of these Guidelines;

.11 time required for un-limiting the SHaPoLi; and

.12 procedures for survey of the SHaPoLi system by the Administration/RO.

.2 EPL:

---CHUNK---

SOURCE: MEPC.335(76).pdf
paragraphs 3.4 and 3.5 of these Guidelines;

.11 time required for un-limiting the SHaPoLi; and

.12 procedures for survey of the SHaPoLi system by the Administration/RO.

.2 EPL:

.1 rated installed power (MCR) or motor output (MPP) and engine speed (NMCR);

.2 limited installed power (MCRlim) or motor output (MPPlim) and engine speed (NMCR,lim);

.3 technical description of the EPL system;

.4 method for sealing the EPL (mechanically controlled engine);

.5 method for locking and monitoring the EPL (electronically controlled engine);

.6 procedures and methods for releasing the EPL;

.7 time required for unlimiting the EPL;

.8 procedures for survey of the EPL system by the Administration/RO;

.9 procedure for the report on release of the EPL; and