1.13 The device should be designed so that on restart following an emergency shutdown the emission limits will normally not be exceeded

Description and basis of how the device has been so designed and how that is demonstrated and maintained in service

1.14 Unless discharged ashore, the discharge water arrangements of the device should be designed to meet the discharge limits under all operating conditions with the waste materials it is designed to process to include those in -service controls and

---CHUNK---

SOURCE: MEPC.373(80).pdf

water arrangements of the device should be designed to meet the discharge limits under all operating conditions with the waste materials it is designed to process to include those in -service controls and measurements used to regulate the device together with emergency shutdown and re-starting procedures

Description and basis of how the discharge water arrangements of the device have been designed and tested to demonstrate in service that the required performance will be achieved under all operating conditions

1.15 Where the nature of the device operating principles results in a discharge water stream with pollution aspects additional to those controlled in section 4 of these Guidelines then those should be duly controlled

Identification of additional discharge water criteria applicable to the operating principle applied and how those are controlled in order to meet the requirements of regulation 4.4 of MARPOL Annex VI

1.16 The capacity of the device (minimum and maximum) should be stated and should be such that when operating at any point in that range the emission limits would not be exceeded

How that capacity range has been

---CHUNK---

SOURCE: MEPC.373(80).pdf
MARPOL Annex VI
1.16 The capacity of the device (minimum and maximum) should be stated and should be such that when operating at any point in that range the emission limits would not be exceeded
How that capacity range has been established and demonstrated

1.17 All different capacity options/models of the device should meet the emission limits
How those capacity ranges have been established and demonstrated
1.18 The design of the device should be defined and there should be an agreed conformity of production arrangement to ensure each unit as delivered will not exceed the emission limits in service

Each unit should be identified in a manner which provides for its inclusion under the approval given together with its waste handling capacity (MW or as applicable)
Device definition and proposed conformity of production arrangement and how that is to be audited/inspected to ensure ongoing consistency with that definition
1.19 There should be a means of unit certification
Proposed means by which each unit will be certified and how that is to
RESOLUTION MEPC.373(80) (adopted on 7 July 2023)

---CHUNK---

SOURCE: MEPC.373(80).pdf
audited/inspected to ensure ongoing consistency with that definition
1.19 There should be a means of unit certification
Proposed means by which each unit will be certified and how that is to
RESOLUTION MEPC.373(80) (adopted on 7 July 2023)
2023 GUIDELINES FOR THERMAL WASTE TREATMENT DEVICES (TWTD)MEPC 80/17/Add.1
Annex 8, page 11

I:\MEPC\80\MEPC 80-17-Add.1.docx
Functional objective Content of TWTD Technical Report

function between the applicant and
the Administration leading to the issue
of individual TWT Device Certificates
1.20 Where there are design/manufacturing
changes after approval as an equivalent
means that affect the emissions
performance of the device, those changes
should be approved before being applied
to devices to be considered for certification
under that approval
Proposed change management
process and how that will function to
ensure that changes are not
introduced to certified devices prior to
their acceptance by the
Administration
1.21 Additional device design and/or
manufacture related Functional Objectives
as applicable to this type of device which
are relevant in terms of meeting the

---CHUNK---

SOURCE: MEPC.373(80).pdf
introduced to certified devices prior to
their acceptance by the
Administration
1.21 Additional device design and/or
manufacture related Functional Objectives
as applicable to this type of device which
are relevant in terms of meeting the
emission limits and the objectives of
regulation 4.4 of MARPOL Annex VI
should be identified
Resolution of those additional
Functional Objectives
2. Installation on board

2.1 The installation on board should be such
that the device performance is as required
The onboard installation
requirements, including if applicable
discharge water arrangements, to
ensure that the performance of the
device is not adversely affected by,
but not limited to, heat, vibration, ship
movement or the functioning of other
equipment. How it is demonstrated,
by post installation tests or other
means, that these requirements have
been met
2.2 The exhaust duct arrangements and
fittings should be such that the device
performance is as required

The design, arrangement and installation requirements of the exhaust duct design from the device to atmosphere to ensure that the performance of the device is not adversely affected.

---CHUNK---

SOURCE: MEPC.373(80).pdf
performance is as required
The design, arrangement and installation requirements of the exhaust duct design from the device to atmosphere to ensure that the performance of the device is not adversely affected.
All necessary connections for operating features, monitoring devices and control arrangements to be positioned as necessary.

The means by which it is