demonstrated these have been met
2.3 The necessary supply services (fuel, air, compressed air, electrical, etc.) for the device to operate as required should be provided
Listing of all the requirements in respect of those support services necessary for the correct operation and performance of the device including any associated discharge water arrangements.

The means by which it is demonstrated that these have been met

Functional objective Content of TWTD Technical Report
2.4 Installation test demonstrating that the device performance is as required including that of any discharge water arrangements

---CHUNK---

SOURCE: MEPC.373(80).pdf

I:\MEPC\80\MEPC 80-17-Add.1.docx
Functional objective Content of TWTD Technical Report
2.4 Installation test demonstrating that the device performance is as required including that of any discharge water arrangements
Installation test procedures which are to be applied and associated acceptance criteria
2.5 Additional device installation related Functional Objectives as applicable to this type of device which are relevant in terms of meeting the emission limits and the objectives of regulation 4.4 of MARPOL Annex VI should be identified
Resolution of those additional Functional Objectives
3. In-service operation

3.1 When in an idle condition there should not be any significant emissions from the

device (these systems can be difficult to quickly shut completely on and off and thus may require an idle status when they do not receive any feedstock)
Means by which this requirement is achieved or basis on which this is not applicable
3.2 The warm-up phase should ensure that on completion the device will operate as required
Means by which this requirement is achieved
3.3 The preparation of solid waste (sorting,

---CHUNK---

SOURCE: MEPC.373(80).pdf
achieved or basis on which this is not applicable
3.2 The warm-up phase should ensure that on completion the device will operate as required
Means by which this requirement is achieved
3.3 The preparation of solid waste (sorting, size screening etc.) should be such that the device will operate as required
Operating procedures in respect of the preparation of solid waste
3.4 The preparation of liquid wastes/sludge oil should be such that the device will operate as required
Operating procedures in respect of the preparation of liquid wastes
3.5 The preparation of sewage sludge should be such that the device will operate as required
Operating procedures in respect of the preparation of sewage waste
3.6 The procedure for loading solid waste should be such that the device performs as required
Operating procedures in respect of the loading of solid waste into the device
3.7 The procedure for loading liquid waste should be such that the device performs as required
Operating procedures in respect of the loading of liquid waste into the device
3.8 The procedure for loading sewage sludge should be such that the device performs as required

---CHUNK---

SOURCE: MEPC.373(80).pdf
should be such that the device performs as required
Operating procedures in respect of the loading of liquid waste into the device
3.8 The procedure for loading sewage sludge should be such that the device performs as required
Operating procedures in respect of the loading of sewage waste into the device
3.9 If applicable the procedure for concurrently loading solid waste, liquid waste or sewage sludge should be such that the device performs as required
Operating procedures in respect of the concurrent loading of solid waste, liquid waste or sewage waste into the device
3.10 When processing solid waste, the emission to air should be controlled to not exceed the emission limits
Operating procedures for the disposal of solid waste
3.11 When processing liquid waste, the emission to air is to be controlled to not exceed the emission limits
Operating procedures for the disposal of liquid waste
3.12 When processing sewage sludge, the emission to air should be controlled to not exceed the emission limits
Operating procedures for the disposal of sewage sludge
RESOLUTION MEPC.373(80) (adopted on 7 July 2023)

---CHUNK---

SOURCE: MEPC.373(80).pdf
of liquid waste
3.12 When processing sewage sludge, the emission to air should be controlled to not exceed the emission limits
Operating procedures for the disposal of sewage sludge
RESOLUTION MEPC.373(80) (adopted on 7 July 2023)

Functional objective	Content of TWTD Technical Report
3.13 If applicable - when concurrently disposing of solid waste, liquid waste or sewage sludge the emission to air should be controlled to not exceed the emission limits	Operating procedures when operating concurrently on solid waste, liquid waste or sewage sludge
3.14 The loading of further waste material should not result in one or more of the emission limits being exceeded	Operating procedures in respect of loading additional solid waste, liquid waste or sewage sludge while the device is in operation
3.15 The device should demonstrate ongoing compliance with the emission limits to air at all times when in operation, including warm-up and shutdown phases	Means by which ongoing compliance with the emission limits is to be