a new ship is put in service and before the
International Energy Efficiency Certificate is issued. The survey shall verify
8 Refer to the Code for Recognized Organizations (RO Code) (resolutions MSC.349(92) and MEPC.2
37(65)).
Refer also to the Survey Guidelines under the Harmonized System of Survey and Certification (HS
SC), 2023
(resolution A.1186(33)).
9 Refer to the 2022 Guidelines on survey and certification of the Energy Efficiency Design Ind
ex (resolution
MEPC.365(79), as amended by resolutions MEPC.374(80) and MEPC.403(83); and the 2022 Guidelines
on survey and certification of the attained Energy Efficiency Existing Ship Index (EEXI)
(resolution MEPC.351(78)).
RESOLUTION MEPC.403(83) (adopted on 11 April 2025)
---CHUNK---
SOURCE: MEPC.403(83).pdf
on survey and certification of the attained Energy Efficiency Existing Ship Index (EEXI)
(resolution MEPC.351(78)).
RESOLUTION MEPC.403(83) (adopted on 11 April 2025)
AMENDMENTS TO THE 2022 GUIDELINES ON SURVEY AND CERTIFICATION
OF THE ENERGY EFFICIENCY DESIGN INDEX (EEDI)MEPC 83/17/Add.1
Annex 11, page 13
I:\MEPC\MEPC 83-17-Add.1.docx
that the ship's attained EEDI is in accordance with the requirements in
chapter 4 of this Annex, and that the SEEMP required by regulation 26 of this
Annex is on board;
.2 a general or partial survey, according to the circumstances, carried out after a
major conversion of a new ship to which this regulation applies. The survey
shall ensure that the attained EEDI is recalculated as necessary and meets
the requirement of regulation 24 of this Annex, with the reduction factor
applicable to the ship type and size of the converted ship in the phase
corresponding to the date of contract or keel laying or delivery determined for
the original ship in accordance with regulation 2.2.16 of this Annex;
.3 in cases where the major conversion of a new or existing ship is so extensive
---CHUNK---
SOURCE: MEPC.403(83).pdf
corresponding to the date of contract or keel laying or delivery determined for
the original ship in accordance with regulation 2.2.16 of this Annex;
.3 in cases where the major conversion of a new or existing ship is so extensive
that the ship is regarded by the Administration as a newly constructed ship, the
Administration shall determine the necessity of an initial survey on attained
EEDI. Such a survey, if determined necessary, shall ensure that the attained
EEDI is calculated and meets the requirement of regulation 24 of this Annex,
with the reduction factor applicable corresponding to the ship type and size of
the converted ship at the date of the contract of the conversion, or in the
absence of a contract, the commencement date of the conversion. The survey
shall also verify that the SEEMP required by regulation 26 of this Annex is on
board and, for a ship to which regulation 27 applies, has been revised
appropriately to reflect a major conversion in those cases where the major
conversion affects data-collection methodology and/or reporting processes;
.4 for existing ships, the verification of the requirement to have a SEEMP on
---CHUNK---
SOURCE: MEPC.403(83).pdf
appropriately to reflect a major conversion in those cases where the major
conversion affects data-collection methodology and/or reporting processes;
.4 for existing ships, the verification of the requirement to have a SEEMP on
board according to regulation 26 of this Annex shall take place at the first
intermediate or renewal survey identified in paragraph 1 of this regulation,
whichever is the first, on or after 1 January 2013;
.5 the Administration shall ensure that for each ship to which regulation 27 applies,
the SEEMP complies with regulation 26.2 of this Annex. This shall be done
prior to collecting data under regulation 27 of this Annex in order to ensure the
methodology and processes are in place prior to the beginning of the ship's
first reporting period. Confirmation of compliance shall be