…)

.3 the required EEDI of Phase 2 is applied to the following new ship:

.1 for ship types where Phase 2 ends on 31 March 2022∗:

.1 the building contract of which is placed in Phase 2, and the

delivery is before 1 April 2026; or

∗ Unified Interpretation is applicable when resolution MEPC.324(75) enters into force on 1 April 2022.

.2 the building contract of which is placed before Phase 2,

and the delivery is on or after 1 January 2024 and

before 1 April 2026; or

in the absence of a building contract:

.3 the keel of which is laid or which is at a similar stage of

construction on or after 1 July 2020 and before 1 October

2022, and the delivery is before 1 April 2026; or

.4 the keel of which is laid or which is at a similar stage of

construction before 1 July 2020, and the delivery is on or

-

construction on or after 1 July 2020 and before 1 October

2022, and the delivery is before 1 April 2026; or

.4 the keel of which is laid or which is at a similar stage of

construction before 1 July 2020, and the delivery is on or

after 1 January 2024 and before 1 April 2026.

.2 for ship types where Phase 2 ends on 31 December 2024:

.1 the building contract of which is placed in Phase 2, and the

delivery is before 1 January 2029; or

.2 the building contract of which is placed before Phase 2,

and the delivery is on or after 1 January 2024 and before

1 January 2029; or

in the absence of a building contract:

.3 the keel of which is laid or which is at a similar stage of

construction on or after 1 July 2020 and before 1 July 2025,

and the delivery is before 1 January 2029; or

.4 the keel of which is laid or which is at a similar stage of

construction before 1 July 2020, and the delivery is on or

after 1 January 2024 and before 1 January 2029.

.4 the required EEDI of Phase 3 is applied to the following new ship:

.1 for ship types where Phase 3 commences with 1 April 2022 and

onwards:

.1 the building contract of which is placed in Phase 3; or

-

.4 the required EEDI of Phase 3 is applied to the following new ship:

.1 for ship types where Phase 3 commences with 1 April 2022 and

onwards:

.1 the building contract of which is placed in Phase 3; or

.2 the building contract of which is placed before Phase 3,

and the delivery is on or after 1 April 2026; or

in the absence of a building contract:

.3 the keel of which is laid or which is at a similar stage of

construction on or after 1 October 2022; or

.4 the keel of which is laid or which is at a similar stage of

construction before 1 October 2022 and the delivery of

which is on or after 1 April 2026.

.2 for ship types where Phase 3 commences with 1 January 2025 and

onwards:

.1 the building contract of which is placed in Phase 3; or

.2 the building contract of which is placed before Phase 3,

-

Annex 6, page 3

I:\MEPC\76\MEPC 76-15-Add.2.docx

.1 the building contract of which is placed in Phase 3; or

.2 the building contract of which is placed before Phase 3,

and the delivery is on or after 1 January 2029; or

in the absence of a building contract:

.3 the keel of which is laid or which is at a similar stage of

construction on or after 1 July 2025; or

.4 the keel of which is laid or which is at a similar stage of

construction before 1 July 2025 and the delivery of which

is on or after 1 January 2029.

(……)

***

RESOLUTION MEPC.332(76) (adopted on 17 June 2021)

EFFICIENCY DESIGN INDEX (EEDI) FOR NEW SHIPS (RESOLUTION MEPC.308(73), AS AMENDED BY RESOLUTION MEPC.322(74))RESOLUTION MEPC.332(76) (adopted on 17 June 2021)

EFFICIENCY DESIGN INDEX (EEDI) FOR NEW SHIPS (RESOLUTION MEPC.308(73), AS AMENDED BY RESOLUTION MEPC.322(74))

-