hall specify how to operate the incinerator within the limits described

in paragraph 2 of appendix IV of this Annex.

38 Type Approval Certificates issued taking into account the Revised guidelines for the implementation of

Annex V of MARPOL (resolution MEPC.59(33), as amended by resolution MEPC.92(45)), or Standard

specification for shipboard incinerators (resolution MEPC.76(40), as amended by resolution MEPC.93(45)),

or the 2014 Standard specification for shipboard incinerators (resolution MEPC.244(66)), as amended by

resolution MEPC.368(79).

39 Refer to the 2014 Standard specification for shipboard incinerators (resolution MEPC.244(66), as amended

by resolution MEPC.368(79)), or Standard specification for shipboard incinerators (resolution MEPC.76(40),

as amended by resolution MEPC.93(45)), and Type approval of shipboard incinerators (MEPC.1/Circ.793).

RESOLUTION MEPC.403(83) (adopted on 11 April 2025)

OF THE ENERGY EFFICIENCY DESIGN INDEX (EEDI)MEPC 83/17/Add.1

-

RESOLUTION MEPC.403(83) (adopted on 11 April 2025)

OF THE ENERGY EFFICIENCY DESIGN INDEX (EEDI)MEPC 83/17/Add.1

Annex 11, page 34

I:\MEPC\MEPC 83-17-Add.1.docx

8 Personnel responsible for the operation of an incinerator installed in accordance with

the requirements of paragraph 6.1 of this regulation shall be trained to implement the guidance

provided in the manufacturer's operating manual as required by paragraph 7 of this regulation.

9 For incinerators installed in accordance with the requirements of paragraph 6.1 of this

regulation the combustion chamber gas outlet temperature shall be monitored at all times the

unit is in operation. Where that incinerator is of the continuous -feed type, waste shall not be

fed into the unit when the combustion chamber gas outlet temperature is below 850°C. Where

that incinerator is of the batch-loaded type, the unit shall be designed so that the combustion

chamber gas outlet temperature shall reach 600 °C within five minutes after start -up and will

thereafter stabilize at a temperature not less than 850°C.

Regulation 17

Reception facilities

-

chamber gas outlet temperature shall reach 600 °C within five minutes after start -up and will

thereafter stabilize at a temperature not less than 850°C.

Regulation 17

Reception facilities

1 Each Party undertakes to ensure the provision of facilities adequate to meet the:

.1 needs of ships using its repair ports for the reception of ozone -depleting substances and equipment containing such substances when removed from ships;

.2 needs of ships using its ports, terminals or repair ports for the reception of exhaust gas cleaning residues from an exhaust gas cleaning system;

without causing undue delay to ships, and

.3 needs in ship -breaking facilities for the reception of ozone -depleting substances and equipment containing such substances when removed from ships.

2 The following States may satisfy the requirements in paragraph 1 of this regulation through regional arrangements when, because of those States ' unique circumstances, such arrangements are the only practical means to satisfy these requirements:

.1 small island developing States; and

.2 States the coastline of which borders on Arctic waters, provided that regional

-

arrangements are the only practical means to satisfy these requirements:

.1 small island developing States; and

.2 States the coastline of which borders on Arctic waters, provided that regional arrangements shall cover only ports within Arctic waters of those States.

3 Parties participating in a regional arrangement shall develop a Regional Reception Facilities Plan, taking into account the guidelines developed by the Organization. 40 The Government of each Party participating in the arrangement shall consult with the Organization,

for circulation to the Parties of the present Convention, on:

.1 how the Regional Reception Facilities Plan takes into account the guidelines developed by the Organization;41

40 Refer to the 2012 Guidelines for the development of a Regional Reception Facilities Plan (resolution MEPC.221(63), as amended by resolution MEPC.363(79)).

41 Refer to the 2012 Guidelines for the development of a Regional Reception Facilities Plan (resolution MEPC.221(63)), as amended by resolution MEPC.363(79).

-

(resolution MEPC.221(63)), as amended by