and to which chapter 4 is applicable: (……) .3 the required EEDI of Phase 2 is applied to the following new ship: .1 for ship types where Phase 2 ends on 31 March 2022∗: .1 the b uilding contract of which is placed in Phase 2, and the delivery is before 1 April 2026; or ∗ Unified Interpretation is applicable when resolution MEPC.324(75) enters into force on 1 April 2022.

RESOLUTION MEPC.332(76) (adopted on 17 June 2021) AMENDMENTS TO THE 2018 GUIDELINES ON T HE METHOD OF CALCULATION OF THE ATTAINED ENERGY EFFICIENCY DESIGN INDEX (EEDI) FOR NEW S HIPS (RESOLUTION MEPC.308(73), AS AMENDED BY RESOLUTION MEPC.322(74))MEPC 76/15/Add.12 A nnex 6, page 2 I:\MEPC\76\MEPC 76-15-Add.2.docx .2 the building contract of which is pla ced before Phase 2, and the delivery is on or after 1 January 2024 and before 1 April 20 26; or in the absence of a building contract: .3 the keel of which is laid or which is a t a similar stage of construction on or after 1 July 2020 and before 1 October 2022, and the delivery is before 1 April 2026; or .4 the keel of which is laid or which is at a si milar stage of construction before 1 July 2020, and the delivery is on or - construction on or after 1 July 2020 and before 1 October 2022, and the delivery is before 1 April 20 26; or .4 the keel of which is laid or which is at a similar stage of construction befor e 1 July 2020, and the delivery is on or after 1 January 2024 and before 1 April 2026.

.2 for ship types where Phase 2 ends on 31 December 2024: .1 the building contract of wh ich is placed in Phase 2, and the delivery is before 1 January 2029; or .2 the building contract of which is placed before Phase 2, and the delivery is on or after 1 January 20 24 and before 1 January 2029; or in the absence of a building contract: .3 the keel of w hich is laid or which is at a similar stage of construction on or after 1 July 2020 and before 1 July 2025, and the delivery is before 1 January 2029; or .4 the keel of which i s laid or which is at a similar stage of construction before 1 July 2020, and the delive ry is on or after 1 January 2024 and before 1 January 2029.

.4 the required EEDI of Phase 3 is applied to the following new ship: .1 for ship types where Phase 3 commences with 1 April 2022 and onwards: .1 the building contract of which is placed in Phase 3; or - .4 the required EEDI of Phase 3 is applied to the following n ew ship: .1 for ship types where Phase 3 commences with 1 April 2022 and onwards: .1 the building contract of which is placed in Phase 3; or .2 the building contract of which is placed before Phase 3, and the delivery is on or after 1 April 2026; or in the absence o f a building contract: .3 the keel of which is laid or which is at a similar stage of co nstruction on or after 1 October 2022; or .4 the keel of which is laid or which is at a similar stage of construction before 1 October 2022 and the delivery of which is on or a fter 1 April 2026.

.2 for ship types where Phase 3 commences with 1 January 2025 and onwards: RESOLUTION ME PC.332(76) (adopted on 17 June 2021) AMENDMENTS TO THE 2018 GUIDELINES ON THE METHOD OF CALCULATION OF THE ATTAINED ENERGY EFFI